

December 3, 2009

**ST. PAUL LUTHERAN CHURCH  
NEWARK, OHIO**

Original Wicks organ Opus #3104, 11 ranks, Choir ranks prepared for, built in 1951, cost \$10,658.50.

<u>GREAT</u>			<u>SWELL</u>		
8'	Open Diapason	73 Pipes	16'	Lieblich Gedeckt	
8'	Melodia	73 Pipes	8'	Violin Diapason	73 Pipes
8'	Gemshorn	73 Pipes	8'	Stopped Flute	85 Pipes
8'	Dulciana	85 Pipes	8'	Salicional	73 Pipes
4'	Octave		8'	Aeoline	73 Pipes
4'	Flute		4'	Flute d'Amour	
4'	Gambette		4'	Violin	
4'	Dolce		4'	Aeoline	
2 2/3'	Dulciana Twelfth		2 2/3'	Nazard	
2'	Dulciana Fifteenth		2'	Piccolo	
8'	Trumpet	61 Pipes	8'	Oboe	61 Pipes
	Chimes (prepared)			Tremolo	
<u>CHOIR</u>			<u>PEDAL</u>		
8'	Violin Diapason (prepared)		16'	Open Diapason (Great)	12 Pipes
8'	Clarabella Flute (prepared)		16'	Bourdon	32 Pipes
8'	Viola (Great Gemshorn)		16'	Lieblich Gedeckt (Swell)	12 Pipes
8'	Dulciana (Great)		8'	Diapason (Swell)	
8'	Unda Maris (prepared)		8'	Bass Flute (prepared)	
4'	Flute (prepared)		8'	Cello (Swell)	
8'	Clarinet (prepared)		8'	Dolce Flute (Swell)	

The organ was purchased in 1950; according to the Wicks salesman "...these ladies are very ambitious having practically all the money for the present organ and hoping to complete the rest in two or three years..." In January 1951 Wicks quoted \$769 for grilles, but in the end these were purchased locally. The organ was delivered on March 30, 1951, but by May 5 it was still impossible to install it because of the "defective radiant heating system" in the new building. On May 22 the Church's Treasurer wrote that "...construction on the Church has been held up because of a strike at the stone quarry..." The installation was finally completed in October, 1951.

In February 1954 the following ranks were installed to complete the Choir, at a cost of \$4,515.00:

8'	Geigen Diapason	73 Pipes
8'	Clarabella	85 Pipes
8'	Viola	73 Pipes
8'	Unda Maris TC	61 Pipes
8'	Clarinet	73 Pipes

This brought the total to 16 ranks. In 1982 further additions were purchased, plus a new Relay System, a new Combination Action, and some other smaller repairs, for a total of \$53,430.00. There were 7 ranks of new pipes, two of which replaced older ones, for a net gain of 5 ranks to a total of 21. This work was completed in September, 1982, and the additions were all in the Great, so the Great stolist now read:

8'	Principal	61 Pipes [NEW]
8'	Holzgedeckt	61 Pipes [NEW]
8'	Gemshorn	73 Pipes
8'	Dulciana	85 Pipes
4'	Octave	61 Pipes [NEW]
4'	Flute	
4'	Gambette	
4'	Dolce	
2'	Super Octave	61 Pipes [NEW]
III	Mixture	183 Pipes [NEW]
8'	Trumpet	61 Pipes
	Chimes (prepared)	

In 2002 the Church advised that they were replacing their "aging and failing radiant floor heating system..." In 2008 a solid-state system apparently was installed by another firm, and our file ends there.

*John E. Spurling*  
Tonal Director Emeritus